### **Energy Conservation Plan – Phase 2**





### **Project Overview**

Annual District Energy Savings: \$173,194 Project Cost: \$3,336,396

Facility Improvement Measures (FIM):

10

Payback Period: **17.9 years** 

Savings Guarantee: 100%

**Energy Conservation Measures** 





# **Energy Conservation Measures – Energy Management System - Extension**

- Removal of Andover System- HS, Bell and Roaring Brook
- Improved control, Reduced Maintenance

#### **District Wide Energy Management System**









# **Energy Conservation Measures – Pipe and Valve Insulation**

- Pipe and Valve insulation in all the buildings not covered in phase 1
- All Areas in unconditioned spaces (per SED standards).

#### **Existing Un-insulated Heating Distribution System**







# **Energy Conservation Measures – Boiler/Burner Replacement**



- Dual fuel natural gas boiler at Horace Greeley High School
- Natural Gas Supply from Main to Building.
- Demolition of existing boiler
- 2 Unilux Boilers high efficiency low pressure steam boilers. 90% efficiency.

Annual Savings: \$90,371

### **Energy Conservation Measures – Window Film**

- Vista Low Emissivity series VE-50 Window Film at all the buildings
- Total Window Area Covered: 81,169 square feet districtwide

SQUARE FT.	DESCRIPTION	
9,153	Douglas Graflin School 3,664	N-2,045 S-1,312 E-2,132 W-
7,856	Bell Middle School	N-360 S-1,807 E-4,866 W-823
15,246	Seven Bridges School	N-5,764 S-8,370 E-440 W-672
8,758	Roaring Brook Elementary	N-597 S-748 E-3,576 W-3,837
4,602	West Orchard Elementary	N-1,659 S-375 E-1,187 W-1,381
35,554	HG High School N-6,249 NW-8,951 NE-3,417 SW-4,815 SE-5,773	
	S-1,098 E-5,251	



### **Energy Conservation Measures - Other Measures**

- Water Conservation— Savings \$11,381
- Motor Replacements Bell and W Orchard Savings \$868
- Vending Machine Controls -13 machines Savings \$1,431
- Plug Load Controllers Savings \$34,043
- Fuel Catalyzer Installation Savings \$9,277
- Transformers Replacements 7 Bridges and Roaring Brook Savings \$5,549



### **Project Timeline**

BOE to Authorize EPC: July 2015

JCI to provide design criteria to ECG: Sept 2015

ECG to prepare submission to SED: Sept - Nov 2015

SED Approval & Financing: Aug - Oct 2016

Construction commences: Nov 2016

Construction substantial completion: September 2017

Final Completion: October 2017

